

INSTRUCTIONS

**NOTE: DO NOT MIX THIS PRODUCT WITH ANY OTHER PRODUCT.
ONLY USE WATER AS A DILUTING SOLUTION (IF REQUIRED)**

SEPTIC / CESSPOOL WITH NO DISTRIBUTION BOX

Dose via Toilet: Break/cut open water-soluble packet and flush the OxyCal down the toilet in 2 flushes by flushing ½ of the packet each flush. Flush toilet 1 final time after complete.

Dose Directly to Septic Tank/Cespool or Cleanout: Put entire packet directly into the tank. If you are adding through a cleanout pour 2-3 gallons of water in after adding OxyCal or flush toilet 1-2 times.

SEPTIC WITH ACCESS TO DISTRIBUTION BOX

Dose Septic Tank: Break/cut open water-soluble packet and flush ½ of the OxyCal down the toilet. If you have access to your tank you can pour ½ directly into the tank or cleanout. Flush toilet 1-2 times if administering through cleanout.

Dose Distribution Box: Pour the remaining OxyCal directly into the distribution box or mix the remaining OxyCal with 3-5 gallons of water and pour the solution directly into the distribution box. Wait 6-8 hours and begin treatment with our septic product(s).

FOR SEVERE LEACHFIELD PROBLEMS AND BIOMAT BUILDUP

DOSING PROCEDURE: Drop the entire water-soluble packet into the distribution box or mix the entire water-soluble packet in 3-5 gallons of water and pour solution directly into distribution box.

Wait 6-8 hours and begin treatment with our septic product(s).



OxyCal

Oxygen Generating Compound

Cumming, Georgia 30028 USA

770-886-1461

www.rex-bac-t.com